

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

For corners in

KALKASKA Located In: Corner Code #  
(County)  
1999 REMONUMENTATION  
1. Public Land Survey T 25N R 8W C-6  
T      R       
T      R       
T      R       
2. Property Controlling S      T      R       
in Section S      T      R       
3. Miscellaneous S      T      R       
Property in Sec. S      T      R     

MAR 01 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on November 8, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6: 1/4 Cor. Common to Sec. 17 & 18, T25N-R8W, Springfield Township

1852, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co. Survey Notes, Pg. 308, set 1/4 Section corner, B. Ash, 12", N39°E, 11 Lks; B. Ash, S20°W, 3 Lks

1981 & 1996, Survey, by E. Farrier (Co. Surveyor), found 1" bar in centerline of road: N35°W, 8" Elm, 51.43'; N70°W, 6" Cedar, 44.44'; S35°W, 12" Y. Birch, 69.58'; S35°E, 5" Pincherry, 72.00'



Kalkaska County Joan Hall, Register

3020115

Page: 1 of 1

02/04/2000 03:08P

REMON

LB: 8 PG: 61

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6: 1/4 Cor. Common to Sec. 17 & 18, T25N-R8W, Springfield Township

Found 1" X 8" piece of old axle shaft, 1' East of centerline of N-S road.

N60°E, 45.60', 3" Cedar, set nail & washer  
S65°E, 49.52', 10" Poplar, set nail & washer  
N85°W, 36.63', 6" Ash, set nail & washer  
N35°W, 56.30', 6" Elm, set nail & washer  
No G.L.O. witnesses were found.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6: 1/4 Cor. Common to Sec. 17 & 18, T25N-R8W, Springfield Township

Found 1" X 8" piece of old axle shaft, 1' East of centerline of N-S road. Pulled & set 5/8" X 18" rod w/brass cap in mon. box.

N60°E, 45.60', 3" Cedar, set nail & washer  
S65°E, 49.52', 10" Poplar, set nail & washer  
N85°W, 36.63', 6" Ash, set nail & washer  
N35°W, 56.30', 6" Elm, set nail & washer

Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Signed by Eugene Farrier  
Michigan License No. 24594

Date 02-04-00 Surveyor's