

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1999 REMONUMENTATION		
1. Public Land Survey	T <u>25N</u> R <u>8W</u>	<u>C-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY &
 RE-MONUMENTATION

MAR 01 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on November 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9; Sec. Cor. Common to Sec. 19, 20, 29, 30, T25N-R8W, Springfield Township
 1852, G.L.O. Resurvey, by V.W. Ceukin (Deputy Surveyor) Co. Survey Notes Pg 316, set post corner, Hemlock 20", S47°W, 25 Lks; Hemlock 30", S36°E, 9 Lks
 1904, Sec. Sub. Survey, by W.S. Merrill (Co. Surveyor), found old stake, and set iron stake
 1973, Survey & LCRC, by J.L. Wilcox, (Survey recorded in Liber 1, Pg 888; LCRC recorded in Liber 1, Pg 226, found boat spike in intersection of roads & accepted, N45°W, 73.92', 8" Poplar; N45°E, 83.28', telephone pole; S20°W, 118.04', X in West end of concrete culvert
 1993, Survey, by E. Farrier (Co. Surveyor), found boat spike, S20°W, 118.04' X in W. end conc. culvert, S46°E, 65.16', corner fence post; S49°E, 85.27'; 6" Spruce; N68°W, 76.90', 8" cluster Elm
 1997, Survey, by Farrier Surveying, same wit as Farrier (1993)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9; Sec. Cor. Common to Sec. 19, 20, 29, 30, T25N-R8W, Springfield Township
 Found boat spike inside 1" iron pipe in centerline 4-way road intersection. Pulled boat spike.
 N45°E, 65.25', corner fence post, found nail
 S50°E, 85.22', 8" Spruce, found nail
 S40°W, 51.80', 3" Elm, found nail
 N70°W, 76.93', 7" Elm in clump
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9; Sec. Cor. Common to Sec. 19, 20, 29, 30, T25N-R8W, Springfield Township
 Found boat spike inside 1" iron pipe in centerline 4-way road intersection. Added 5/8" X 18" rod w/ brass cap.
 N45°E, 65.25', corner fence post, found nail
 S50°E, 85.22', 8" Spruce, found nail
 S40°W, 51.80', 3" Elm, found nail
 N70°W, 76.93', 7" Elm in clump
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 02-04-00



3020212
 Page: 1 of 1
 02/08/2000 09:20A
 REMON
 LB: 6 PG: 132