

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

|                                    |                          |               |
|------------------------------------|--------------------------|---------------|
| <u>KALKASKA</u>                    | Located In:              | Corner Code # |
| (County)                           |                          |               |
| <b>1998 REMONUMENTATION</b>        |                          |               |
| 1. Public Land Survey              | T <u>25N</u> R <u>8W</u> | <u>D-3</u>    |
|                                    | T _____ R _____          | _____         |
|                                    | T _____ R _____          | _____         |
|                                    | T _____ R _____          | _____         |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____         |
|                                    | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____         |
|                                    | S _____ T _____ R _____  | _____         |

**SURVEY & REMONUMENTATION**

**FEB 22 1999**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on October 28, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

|    |    |   |    |   |    |   |    |   |    |   |    |
|----|----|---|----|---|----|---|----|---|----|---|----|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  |
| 1  |    |   |    |   |    |   |    |   |    |   |    |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |
| 3  |    |   | ●  |   |    |   |    |   |    |   |    |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |
| 5  |    |   |    |   |    |   |    |   |    |   |    |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |
| 7  |    |   |    |   |    |   |    |   |    |   |    |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |
| 9  |    |   |    |   |    |   |    |   |    |   |    |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |
| 11 |    |   |    |   |    |   |    |   |    |   |    |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |
| 13 |    |   |    |   |    |   |    |   |    |   |    |

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

D-3: 1/4 Cor. Common to Secs. 5 & 8, T25N-R8W, Springfield Township  
 1852, Sub. resurvey by V.W. Cankin D.S.; set corner; Hemlock 22", S 39°E, 24 Lks. (15.84'); Beech 10", N 20°W, 21 Lks. (13.86')  
 1876, Road survey by D.E. McVean CS., Co. Survey Bk. Pg. 2; measured to fd. cor., no accessories  
 1905, Sec. sub. survey by W.S. Merrill CS.; shows cedar stake for cor., no accessories  
 1-26-77, F. Thomson, set 1/2" iron on line by S.P. (LCRC in Liber 2, Pg. 6)  
 5-20-81, E. Farrier, fd 1/2" iron, rod, Cert. of Survey  
 9-17-82, E. Farrier, shows corner only, Cert. of Survey  
 8-2-84, E. Farrier, shows corner only, Liber 2, Pg. 841, Cert. of Survey

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-3: 1/4 Cor. Common to Secs. 5 & 8, T25N-R8W, Springfield Township  
 Fd. and accepted 1/2" iron 3' South of CL road (as recorded in LCRC & Cert. of Surveys). Pulled & set 5/8" X 18" re-bar with brass cap  
 No G.L.O. witnesses were found.  
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**

Chairman Eugene Farrier  
 Date 2-2-99

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-3: 1/4 Cor. Common to Secs. 5 & 8, T25N-R8W, Springfield Township  
 Fd. and accepted 1/2" iron 3' South of CL road. Pulled & set 5/8" X 18" re-bar with brass cap  
 South, 34.90'- Power Pole, found nail  
 North, 33.05'- Iron & Cap #24617  
 N20°E, 57.11'- 12' R. Pine, found nail  
 S65°E, 84.47'- Square Wood Post, set nail



Signed by Eugene Farrier  
 Michigan License No. 24594

Date 2-8-99 Surveyor's



**3012659**

Page: 1 of 1  
 02/10/1999 08:32A

SURVEYORS, JAN. 28, 197  
 REVISED MAY 14, 197  
 REVISED JAN., 198  
 REVISED OCT., 198

LB: 5 PG: 314