

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1998 REMONUMENTATION		
1. Public Land Survey	T <u>25N</u> R <u>8W</u>	<u>E-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &  
 REMONUMENTATION**

**FEB 22 1999**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5	●	4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

I, EUGENE FARRIER, in a field survey on October 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-2: 1/4 Cor. Common to Secs. 4 & 5, T25N-R8W, Springfield Township  
 1852, G.L.O. sub. resurvey by V.W. Cankin D.S.; set corner; Sugar 6", N 10°E, 17 Lks. (11.22'); Beech 12", S 37 1/2°W, 38 Lks. (25.06')  
 1905, Sec. sub. survey by W.S. Merrill CS., FB # 22, Pg. 72; cedar stake and stones for corner; found old gov't bearing tree 9-17-82, E. Farrier, set 1/2" iron & cap #24594 by prorating to Merrill Survey (1905), Cert. of Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-2: 1/4 Cor. Common to Secs. 4 & 5, T25N-R8W, Springfield Township  
 Found and accepted 1/2" iron & cap #24594 in CL road & 2' South of fence to West (as shown in previous Cert. of Surveys) Pulled and set 5/8" X 18" re-bar w/brass cap.  
 N45°E, 56.62' - 12" Beech, found nail  
 No G.L.O. witnesses were found.  
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**  
 Chairman Eugene Farrier  
 Date 2-2-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2: 1/4 Cor. Common to Secs. 4 & 5, T25N-R8W, Springfield Township  
 Found and accepted 1/2" iron & cap #24594 in CL road & 2' South of fence to West. Pulled and set 5/8" X 18" re-bar w/brass cap.  
 S35°E, 45.05' - 10" Twin Elm, set nail & washer  
 N45°E, 56.62' - 12" Beech, found nail  
 S47°W, 50.12' - Wood fence post, set nail & washer  
 N80°W, 33.14' - Power pole, set nail & washer



Signed by Eugene Farrier  
 Michigan License No. 24594

Date 2-8-99 Surveyor's



**3012660**  
 Page: 1 of 1  
 02/10/1999 08:32A

ATIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983  
 REVISED OCT., 1991