

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)  
 1998 REMONUMENTATION  
 1. Public Land Survey T 26N R 8W H-13  
 T 25N R 8W H-1 ✓  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

**FEB 22 1999**

**SECTION**

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on November 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

H-13: 1/4 Cor. Common to Sec. 34, T26N-R8W, Boardman Township, & H-1: 1/4 Cor. Sec. 5, T25N-R8W.

1852, G.L.O. Twp. Line Resurvey by V.W. Cankin D.S.; set post for cor., Hemlock 22", N32°E, 14 Lk. (9.24'); Hemlock 6", N59°W, 33 Lk. (21.78').

1-30-74, J. Fletcher, set 1/2" re-rod by single proportionate measurement. LCRC Liber 1, Pg. 291

1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 465, Cert. of Survey

1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 466, Cert. of Survey

1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 468, Cert. of Survey

1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 469, Cert. of Survey

1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 470, Cert. of Survey

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-13: 1/4 Cor. Common to Sec. 34, T26N-R8W, Boardman Township, & H-1: 1/4 Cor. Sec. 5, T25N-R8W.

Found & accepted iron & cap #19830 in centerline road East extended, and on fence to South (as recorded in LCRC, Liber 1, Pg. 291, an previous Cert. of Surveys)

No G.L.O. witnesses were found.

Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**

Chairman Eugene Farrier

Date 2-2-99

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-13: 1/4 Cor. Common to Sec. 34, T26N-R8W, Boardman Township, & H-1: 1/4 Cor. Sec. 5, T25N-R8W.

Found & accepted iron & cap #19830 in centerline road East extended, and on fence to South (as recorded in LCRC, Liber 1, Pg. 291, an previous Cert. of Surveys) Pulled and set 5/8" X 1 1/8" re-rod w/ brass cap.

North 33.13'- iron & cap #19830

N71°E, 39.23'- 12" W. Pine, set nail & washer

S12°E, 33.92'- Wood fence post, set nail & washer

S55°W, 60.12' - 14" Red Pine, set nail & washer

Signed by Eugene Farrier  
 Michigan License No. 24594

Date 2-8-99

