

# SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>J-13</u>
	T <u>25N</u> R <u>8W</u>	<u>0-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on OCTOBER 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
**J-13:** Cor. Common to Sec. 35, T26N-R8W, Boardman Township, Sec. 2, T25N-R8W, Springfield Township. 1852, GLO resurvey, set post, 16" Sugar N87E 28, 18" Sugar N45W 42  
 09-04-1973, J.L. Wilcox #14102, survey, set 1/2" rod by single prop. w/accessories  
 11-04-1980, Farrier Surveying, survey, field bk. 1, pg. 39, fd. 1/2" rod, no accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**J-13:** Cor. Common to Sec. 35, T26N-R8W, Boardman Township, Sec. 2, T25N-R8W, Springfield Township.  
 Fd. 1/2" x 18" re-rod, w/accessories. Pulled & replaced with 5/8" x 18" re-rod w/brass cap (Inman Rd.) 4' N. Of C.L. gravel rd. & 8' West of fence to North. No GLO witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**J-13:** Cor. Common to Sec. 35, T26N-R8W, Boardman Township, Sec. 2, T25N-R8W, Springfield Township.  
 Fd. 1/2" x 18" re-bar, w/accessories. Pulled & replaced with 5/8" x 18" re-rod w/brass cap. (Inman Rd.) 4' N. Of C.L. gravel rd. & 8' West of fence to N.  
 Set nail & tag N43E, 11" R. Pine 52.45'  
 Set nail & tag South, 12" R. Pine 47.49'  
 Set nail & tag S35W, 12" R. Pine 56.54'  
 Set nail & tag N25W, 5" R. Pine 53.68'

Ratified by Peer Group  
 P.A. 345 - 1990 Kalkaska County  
 Chairman Eugene Farrier  
 Date 1-29-98



Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 2-3-98



**3004855**  
 Page: 1 of 1  
 02/04/98 11:22F  
 LB: 5 PG: 259