

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 RECORDS

For corners in

KALKASKA

(County)

1999 REMONUMENTATION

1. Public Land Survey

Located In:

Corner Code #

T 25N R 8W

L-7

T ___ R ___

T ___ R ___

T ___ R ___

S ___ T ___ R ___

S ___ T ___ R ___

S ___ T ___ R ___

S ___ T ___ R ___

2. Property Controlling
 in Section

3. Miscellaneous
 Property in Sec.



Kalkaska County Jean Hall, Register

MAR 01 2000

SECTION

3020143

Page: 1 of 1
 02/04/2000 03:40P
 REMON
 LB: 6 PG: 89

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on December 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-7: 1/4 Cor. Common to Sec. 13 & 24, T25N-R8W, Springfield Township

1852, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor), Hemlock 24", S47°E, 42 Lks; Hemlock 16", N58°W, 28 Lks



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7: 1/4 Cor. Common to Sec. 13 & 24, T25N-R8W, Springfield Township

Set 5/8" X 36" rerod with aluminum cap midway and on line with SW & SE Section corners, 32' South of E-W fence & 19' East of fence to North.

N15°E, 33.33', 24" Twin Oak, set nail & washer

N80°E, 8.80', 5" Maple, set nail & washer

S40°W, 26.02', 7" Basswood, set nail & washer

N45°W, 16.06', 6" Maple, set nail & washer

No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 02-03-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7: 1/4 Cor. Common to Sec. 13 & 24, T25N-R8W, Springfield Township

Set 5/8" X 36" rerod with aluminum cap midway and on line with SW & SE Section corners, 32' South of E-W fence & 19' East of fence to North.

N15°E, 33.33', 24" Twin Oak, set nail & washer

N80°E, 8.80', 5" Maple, set nail & washer

S40°W, 26.02', 7" Basswood, set nail & washer

N45°W, 16.06', 6" Maple, set nail & washer

Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

Signed by Eugene Farrier
 Michigan License No. 24594

Date 02-04-00 Surveyor's