

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA Located In: Corner Code #  
 (County)  
 1998 REMONUMENTATION  
 1. Public Land Survey T.25N R.8W M-2 ✓  
 T.25N R.7W A-2  
 T. R.  
 T. R.  
 2. Property Controlling S. T. R.  
 in Section S. T. R.  
 3. Miscellaneous S. T. R.  
 Property in Sec. S. T. R.

**SURVEY &  
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIER, in a field survey on October 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-2: 1/4 Cor. Common to Sec. 1, T25N-R8W, Springfield Township, A-2: Sec. 6, T25N-R7W

1839, GLO. Twp., Line Survey by J. P. Alland DS.; set post at corner; Beech 18", S70°W, 27 Lks. (17.82'); Sugar 24", N41°W, 26 Lk (17.16')

1876, Road Survey by D.E. McVean CS., Co. Survey Bk. Pg. 2; measured to fd. cor. no/acc.

1903, Sec. Sub. Survey by W.S. Merrill CS., Co. Survey Bk. Pg. 57; brick buried for corner; Maple 14", N53°W, 41 Lks. (27.06'); Beech 20", S15°W, 53 Lks. (34.98')

1911, 1913, Sec. Sub. Survey by W.S. Merrill CS., Co. Survey FB # 15, Pg. 86; FB # 34, Pg. 8; notes iron at corner, no/acc.

9-5-87, E. Farrier, found 1 1/2" iron pipe 10' East of CL road, Cert. of Survey

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-2: 1/4 Cor. Common to Sec. 1, T25N-R8W, Springfield Township, A-2: Sec. 6, T25N-R7W

Found and accepted 1 1/2" iron pipe 10' East of CL road (as shown in previous Cert. of Surveys) Added 5/8" X 18" re-bar w/brass cap i mon. box

No G.L.O. witnesses were found.

Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

**Ratified by Peer Group  
 P.A. 345 - 1990 Kalkaska County**

Chairman Eugene Farrier

Date 2-2-99

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-2: 1/4 Cor. Common to Sec. 1, T25N-R8W, Springfield Township, A-2: Sec. 6, T25N-R7W

Found and accepted 1 1/2" iron pipe 10' East of CL road. Added 5/8" X 18" re-bar w/brass cap in mon. box

East, 33.00' - iron & cap #24594

S35°E, 38.42' - 28" Maple, set nail & washer

S47°W, 52.30' - 16" Maple, set nail & washer

N68°W, 91.88' - Power pole, set nail & washer

Signed by Eugene Farrier  
 Michigan License No. 24594

Date 2-9-99



**3012684**  
 Page: 1 of 1  
 02/10/1999 08:41A  
 LB: 5 PG: 339

REVISOR, JAN. 28, 1978  
 REVISED MAY 14, 1979  
 REVISED JAN. 1987  
 REVISED OCT., 1988