

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska Located In _____ Corner Code # _____
(County)

- | | | | | |
|--------------------------------------|-------------|--------------|-------------|----------|
| 1. Public Land Survey | T _____ | R _____ | | |
| | T _____ | R _____ | | |
| 2. Property Controlling in Section | S <u>25</u> | T <u>25N</u> | R <u>8W</u> | <u>6</u> |
| | S <u>25</u> | T <u>25N</u> | R <u>8W</u> | <u>9</u> |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | |
| | S _____ | T _____ | R _____ | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 27, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

6 - None

9 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

6 - NE 1/16 Corner Section 25
Set 2" aluminum Cap on 5/8" x 34" rebar per standard BLM procedure. Corner of old fence E, W & S is 25' W.

9 - CE 1/16 Corner Section 25.
Set 2" aluminum Cap on 5/8" x 34" rebar per standard BLM procedure. Remains of N-S fence in 69' E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6 - 2" Aluminum Cap on 5/8" x 34" iron rebar. Set Blue Carsonite Post w/ Loc.tag 1'SW
N9°W 1.60' to set nail & tag in W side 9" Sugar Maple
N89°W 9.71' to set nail & tag in N side 8" Sugar Maple
S22°W 8.42' to set nail & tag in E side 5" Sugar Maple
S83°E 32.07' to set nail & tag in S side 12" Sugar Maple

9 - 2" Aluminum Cap on 5/8" x 34" iron rebar. Set Blue Carsonite Post w/ Loc. tag 1' W
N73°W 10.79' to set nail & tag in SE side Twin 14" Red Maple
S30°W 26.59' to set nail & tag in NW side 16" Red Oak
S50°E 28.02' to set nail & tag in N side 8" Sugar Maple
N28°E 14.90' to set nail & tag in NW side 7" Beech scribed 'XBT'

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													



Signed by:

Craig W. McVean

Date:

7/4/2003

Surveyor's Michigan License No.:

39088