

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska (County)	Located In	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S 25 T 25N R 8W	13	
	S 25 T 25N R 8W	14	
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on May 29, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
13 - None 14 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
13 - SE 1/16 Corner Section 25
 Set 2" aluminum Cap on 5/8" x 34" rebar per standard BLM procedure.
14 - S 1/16 Corner Section 25, T25N, R8W and Section 30, T25N, R7W.
 Set 2" aluminum Cap on 5/8" x 34" rebar per standard BLM procedure - 0.5' below grade in gravel road. Fence line W is 10 ± south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
13 - 2" Aluminum Cap on 5/8" x 34" iron rebar. Set blue carsonite post w/ Loc. tag 1'SW
 S33°W 18.73' to set nail & tag in E side 7" Sugar Maple
 N58°W 14.37' to set nail & tag in S side 9" Red Maple
 N10°E 21.36' to set nail & tag in E side Twin 8" Red Maple
 N76°E 65.22' to set nail & tag in N side 12" Red Maple
14 - 2" Aluminum Cap on 5/8" x 34" iron rebar.
 West 33.00' to set 2" AC on 5/8" x 34" rebar online w/ blue carsonite post w/ Loc. tag
 S20°W 46.02' to set nail & tag in W side Triple 15" Ironwood
 S18°E 88.84' to set nail & tag in E side 10" Red Pine
 S80°E 114.47' to set nail & tag in N side 4" White Pine

Signed by: Craig W. McVean Date: 7/9/2003
 Surveyor's Michigan License No.: 39088