

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska Located In _____ Corner Code # _____
(County)

- | | | | | |
|--------------------------------------|-------------|--------------|-------------|----------|
| 1. Public Land Survey | T _____ | R _____ | | |
| | T _____ | R _____ | | |
| 2. Property Controlling in Section | S <u>26</u> | T <u>25N</u> | R <u>8W</u> | <u>3</u> |
| | S <u>26</u> | T <u>25N</u> | R <u>8W</u> | <u>5</u> |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | |
| | S _____ | T _____ | R _____ | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 29, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
3 - None 5 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
3 - N 1/16th Cor. common to Sec 26 & 27 - Fd. 1/2" x 24" rebar w/cap # 21265. Fits calculated position closely. CIR probably result of 1980 Consumer Power Co. surveys in area. 1/2" CIR accepted as the best available evidence of the position of the corner
5 - CN 1/16th Cor. Section 26 - Set 2" Aluminum cap on 5/8" x 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3 - Replaced 1/2" x 24" CIR with 2" Aluminum cap on 5/8" x 34" rebar. Set Blue Carsonite Post w/ Loc. tag 1' South
 N28°E 5.61' to set nail & tag in W side 9" White Pine
 S53°E 22.77' to set nail & tag in NE side 12" White Pine
 S33°W 18.36' to set nail & tag in E side 16" White Pine
 S88°W 8.17' to set nail & tag in N side 9" White Pine
5 - 2" Aluminum Cap on 5/8" x 34" rebar
 N66°W 12.30' to set nail & tag in SE side Twin 15" Red Oak
 N18°E 48.32' to set nail & tag in E side 4" White Pine
 N82°E 24.98' to set nail & tag in S side 6" White Pine
 S12°E 25.78' to set nail & tag in W side 6" White Pine
 Set Blue Carsonite Post w/ Loc. tag 1' South

Signed by: Craig W. McVean Date: 7/9/2003
 Surveyor's Michigan License No.: 39088