

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Kalkaska Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 26N R 5W H11  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on September 30, 2010 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11							●					
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

H11 – 1852 – GLO – G. Cannon – Set qr. Sec. post,  
1) Y Pine 20" S48°W 18 L.  
2) Y. Pine 22" N27°E 27 L.

- 1957 - DNR Field notes – K.J. Ostling  
Fd. 1/2" bar by Delamater – No action taken

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H11 – 1/4 Corner common to sections 27 & 34, T26N, R5W – No GLO or Delamater evidence was found. Set DNR Monument by single proportion between 'G11' and 'I-11'. Measured grid distances E & W of 2662.89' (2659.14' - GLO). Corner falls at N'y edge of swale ENE – WSW. Measured West 458'± to Top of Hill vs. 443' – GLO and West 812'± to Bottom of Hill vs. 773' – GLO. DNR Monument accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H11 – 4" DNR Alum. Cap on 1" X 36" long galv. iron pipe with ring of stones. Set Blue carsonite Post 1' North.

S88°E 138.44' to set nail & tag in N side 16" Oak scribed 'XBT'  
S68°E 46.40' to set nail & tag in NE side 12" Oak scribed 'XBT'  
S04°E 61.73' to set nail & tag in E side 12" Oak scribed 'XBT'  
S60°W 139.43' to set nail & tag in SE side 10" Oak



Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 1/20/2011