

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W.
26 5 W

Crawford - Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 30, 31, 25, 36

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

12" B. Oak - S20W - 93 links

9" B. Oak - N50W - 130 links

5" B. Oak - N54E - 96 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by single proportionate measurement between original 1/4 corner north and Houghton's file at town corner south, by Forestry Division survey crew while making a survey of these townships.

Corner was placed and witnessed August 5, 1957.

SURVEYORS SEAL

SIGNED *Billy D. Buckles*
REGISTERED LAND SURVEYOR

DATE 10/30/57

