

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Corner common to Sections 17, 18, 19, 20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" R. Pine - S24W - 192 links

14" Double Maple - N16 $\frac{1}{2}$ E - 259 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew, by double proportionate measure, while making a partial resurvey of this township.

Corner was placed and witnessed Nov. 10, 1955.

SURVEYORS SEAL

SIGNED *Billy D. Buckles*
REGISTERED LAND SURVEYOR

DATE 3/12/56