

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Corner common to Sections 26, 27, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" Wt. Oak - S42E - 39 links

7" Wt. Oak - N31E - 52 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Probable original corner with both stumps in place, but burned. The stumps of the old corner, which was 75 links north and 240 links east are in place, but the NE stump bears N25W instead of N25E. This stump has what appears to be a partial face and notch.

Corner was placed and witnessed July 5, 1956

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 7/23/56
REGISTERED LAND SURVEYOR