

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W.

Kalkaska

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 11 & 12

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

8" J. Pine - N59W - 48 1/2 links


10" J. Pine - N44E - 38 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between DeLamater's section corner north and original section corner south by Forestry Division survey crew while making a survey in this area.

Corner was placed and witnessed July 1, 1957.

SURVEYOR'S SEAL



SIGNED Billy D. Duckles  
REGISTERED LAND SURVEYOR

DATE 7/26/57