

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 27 & 28

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

9" Cherry - S63W - 13 1/2 links

Old NBT 26" W. Pine stump N56E - 66 links


Old NBT 24" W. Pine stump N44W - 75 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this township. Found a 1/2" iron bar in place, NBT'd and presumably set by G. F. DeLamater of Gaylord. Checks good for distance south to stream and section corner. Left 1/2" bar in place and set corner beside bar. A 1" pipe is N33W, 55 links, original unknown.

Corner was placed and witnessed July 1, 1957.

SURVEYORS SEAL



SIGNED Billy D. Buckles DATE 7/26/57
REGISTERED LAND SURVEYOR