

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28, 29, 32, 33

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

6" J. Pine - S37W - 66 links

7" J. Pine - N34W - 72½ links


10" J. Pine - N78E - 5½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between section corners 1 mile east, 1 mile west, 1 mile south and 1/2 mile north, by Forestry Division survey crew while making a partial resurvey of this township.

Corner was placed and witnessed June 27, 1957.

SURVEYORS SEAL



SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 7/26/57