

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22, 23, 26, 27

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

- 8" J. Pine - N64E - 62 1/2 links
- 7" J. Pine - N30W - 51 1/2 links
- 8" J. Pine - S17W - 11 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement, by Forestry Division survey crew while making a partial resurvey of this township. Corners 1 mile north, 1 mile south, 1 mile west, and 2 miles east were used in the proportion. No evidence of government Bfs.

Corner was placed and witnessed October 25, 1957

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 12/2/57  
REGISTERED LAND SURVEYOR