

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W. . . .

----- Kalkaska ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13, 14, 23, 24

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER -----

5" W. Birch - S40W - 21 links

5" Balsam - N79E - 25 links

5" W. Birch - N55W - 41 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement by Forestry Division survey crew while making a partial resurvey of this township. Corners 1 mile north,  $2\frac{1}{2}$  miles south, 1 mile east and 1 mile west were used for proportion. A possible position for government corner is 2 links north, but evidence is not conclusive.

Corner was placed and witnessed October 24, 1957.

SURVEYORS SEAL

SIGNED

Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12/2/57