

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 5 W.

Kalkaska

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 23, 24, 25, 26

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

6" J. Pine - N72E - 29 1/2 links

5" J. Pine - S18E - 61 1/2 links

6" J. Pine - S40W - 50 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement by Forestry Division survey crew while making a partial resurvey of this township. Corners 2 miles west, 1 mile east, 1 mile north, and 1 1/2 miles south were used in the proportion. No evidence of government BTs.

Corner was placed and witnessed October 24, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12/2/57

