

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25, 26, 35, 36

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

6" R. Oak - N50E - 41 1/2 links

7" R. Oak - S50W - 16 1/2 links

6" R. Oak - S20E - 20 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement by Forestry Division survey crew while making a partial resurvey of this township. Corners 1/2 mile south, 3 miles north, 1 mile east, and 1 mile west were used in the proportion. Could make no positive identification of small government B.Ts.

Corner was placed and witnessed October 24, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 12/2/57

