

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 10, 11, 14, 15

DESCRIPTION OF CORNER MONUMENT Left 4" square conc. monument in place

WITNESSES TO CORNER

5" J. Pine - S19E - 75 1/2 links

8" J. Pine - S83E - 49 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. No evidence of government BFs, but checks for line and fairly good for distance to 1/4 and section corner south and section corner east. A concrete filled field tile is 92 links west, but this would make the mile east too long.

Corner was placed and witnessed October 28, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 12/2/57