

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14, 15, 22, 23

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

7" W. Birch - S3W - 65 links

10" Cedar - N44E - 55 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found an old stake in swamp which conforms fairly well with a possible NE government BT, the remains of a very large cedar. Also checks fair with 1/4 and section corners west and north. Couldn't be moved to satisfy both line and distance both west and north, for to satisfy one line would be to create a greater error in distance or alignment of the other.

Corner was placed and witnessed October 25, 1957.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*
REGISTERED LAND SURVEYOR

DATE 12/2/57