

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W.

----- Kalkaska ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 21, 22, 27, 28

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER 8" Aspen - N66E - 97 links

6" Aspen - N27W - 73 links

*9" R. Pine - S51E - 197 1/2 links

*24" Y. Pine stump S88E - 128 1/2 links

*G. F. DeLaMater MBT's

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found a 1/2" iron bar 1' below surface faced by witness identified as those of G. F. DeLaMater. This corner checks for line and distance to 1/4 and section corner south, and was obviously used in their location. A 3/4" pipe by Consumers Power Co. is S29W 28 links. No positive identification of OBTs.

Corner was placed and witnessed October 25, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 12/2/57