

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 26 & 27

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

6" W. Oak - S4W - 48 1/2 links

8" R. Pine - N40E - 56 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a partial resurvey of this township. A very old NBT, a 24" R. Pine, stands N8W 90 links from our corner and faces ESE, but can locate no other witness or post, nor record of previous survey. Any point faced by this witness is much too far north when related to the section corner 1/2 mile south.

Corner was placed and witnessed October 25, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 12/2/57