

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

KALKASKA COUNTY, MICHIGAN
RECEIVED

LAND CORNER RECORDATION CERTIFICATE 97 JAN 31 PM 2:26
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| KALKASKA (County) | Located In: | Corner Code # |
|------------------------------------|-------------------------|---------------|
| 1996 REMONUMENTATION | | |
| 1. Public Land Survey | T 26N R 6W | A-3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Joan Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

EUGENE FARRIER, in a field survey on Oct. 21, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- Description of original monument and accessories and/or subsequent restoration:
A-03: Cor. common to Sec. 1 & 12, T26N-R7W, Orange Township, & Sec. 6 & 7, T26N-R6W, Oliver Township
Apr 7, 1839, GLO original survey, set post, T26N-R7W. 8" Birch S52W 19, 8" Maple N60W 23.
GLO original survey, used post, correcting east of T26N-R6W. 5" B. Ash S37E 30, 8" Spruce N63E 70.
09-11-1880, G.A. Limpert, used corner, no accessories.
07-15-1901, W.S. Merrill, used corner, no accessories.
11-09-1972, C.F. Roser, fd. well point added D.N.R. mon., no accessories.
11-09-1972, LCRC Liber 1 pg. 180.
03-24-1973, N.F. Parker, used corner, Liber 1 pg 278.

- Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-03: Cor. common to Sec. 1 & 12, T26N-R7W, Orange Township, & Sec. 6 & 7, T26N-R6W, Oliver Township
Found DNR Mon w/ DNR Cedar Post w/ accessories. Left in place. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

- Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-03: Cor. common to Sec. 1 & 12, T26N-R7W, Orange Township, & Sec. 6 & 7, T26N-R6W, Oliver Township
Found DNR Mon w/ DNR Cedar Post w/ accessories. Left D.N.R. Monument in place 3' South in center line of East-West 5' wide trail.
Set nail & tag N25W 6" Cedar, 19.90'
Set nail & tag N40E 6" Maple, 32.40'
Set nail & tag S50E 10" Maple, 17.14'
Set nail & tag S56W 12" Balsam, 24.52'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *Eugene Farrier*
Date 1-21-97



Signed by *Eugene Farrier* Date 1-30-97
Surveyor's Michigan License No. 24594