

MAR 21 1997

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PM 2: 26

For corner of COMMIS... KALKASKA (County)

Table with columns: Located In, Corner Code #, and rows for 1996 REMONUMENTATION (Public Land Survey, Property Controlling, etc.)

Handwritten signature: Jean Stale REG. OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. ... Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13

I, EUGENE FARRIER, in a field survey on Nov. 21, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-07: Cor. comn to Sec. 13 & 24, T26N-R7W, Orange Township, & Sec. 18 & 19, T26N-R6W, Oliver Township 1849, GLO resurvey, set post. 10" Sugar S19W 19, 10" Sugar N58W 24. May 4, 1852, GLO resurvey, used corner. 20" Yellow Birch S38E 27, 10" Beech N70E 30. Aug 10, 1880, G.A. Himpert, used corner, no accessories. May 1882, E. Mosher, used corner, no accessories. 06-02-1902, W.S. Merrill, used corner, no accessories. 08-29-1904, W.S. Merrill, iron stake, no accessories. 08-27-1905, W.S. Merrill, used corner, no accessories. 05-17-1978, J.L. Wilcox, fd 1/2" rerod. Liber 2 pg. 299 in Survey. May 1978, LCRC Liber 2 pg. 163 06-03-1988, Farrier Surveying, Survey #8388, fd 1/2" rerod; w/ accessories. 07-10-1988, LCRC Liber 2 pg. 382.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-07: Cor. comn to Sec. 13 & 24, T26N-R7W, Orange Township, & Sec. 18 & 19, T26N-R6W, Oliver Township Found 5/8" x 24" iron. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box in c/l Pierson rd. & 1' North of c/l of Spencer rd. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accpeted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-07: Cor. comn to Sec. 13 & 24, T26N-R7W, Orange Township, & Sec. 18 & 19, T26N-R6W, Oliver Township Found 5/8" x 24" iron. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box in c/l Pierson rd. & 1' North of c/l of Spencer rd. N35W stop sign face 36.22' S18E stop sign face 30.85' Set nail & tag N45E cor. fence post 45.32' Set nail & tag S24W 6" elm 96.95'

Vertical text: Ratified by Peer Group P.A. 345 - 1990 Kalkaska County Chairman [Signature] Date 1-31-97

Signed by Eugene Farrier Surveyor's Michigan License No. 24594

Date 1-30-97

