

# SURVEY & REMONUMENTATION

MAR 21 1997

## LAND CORNER RECORDATION CERTIFICATE

KALKASKA COUNTY, MICHIGAN  
RECEIVED

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PM 2:43

For corners in

KALKASKA

(County)

Located In:

Corner Code #

1996 REMONUMENTATION

T 26N R 6W

B-5

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Jean Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

EUGENE FARRIER

in a field survey on Nov. 14, 19 96

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  | ●  |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

1. Description of original monument and accessories and/or subsequent restoration:

B-05 cor common to Sec. 7 & 18, T26N-R6W, Oliver Township  
1852, GLO resurvey, set post, 12" Sugar N80W 13, 12" Yellow Birch S16E 7.  
July 1894, E. Mosher, Co. Surveyor, used corner, no accessories.  
08-29-1904, W.S. Merrill, Co. Surveyor, used corner, no accessories.  
04-17-1911, W.S. Merrill, Co. Surveyor, used corner, no accessories.  
08-29-1975, J.L. Fletcher, used corner, no accessories.  
6-03-1988, Farrier Surveying, Survey #8388, set iron & cap #30079 by doubling over fd C/4 & fd N/8 w/ accessories.  
06-10-1988, LCRC Liber 2 pg. 388.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-05 cor common to Sec. 7 & 18, T26N-R6W, Oliver Township  
Found 1/2" x 18" re-rod w/ cap #30079 w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 2' North of centerline of Cool Road & 73' West of Red Pine occupation line. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 1-21-97

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-05 cor common to Sec. 7 & 18, T26N-R6W, Oliver Township  
Found 1/2" x 18" re-rod w/ cap #30079 w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 2' North of centerline of Cool Road & 73' West of Red Pine occupation line.  
Set nail & tag N45E 8" R. Pine, 114.65'  
Set nail & tag N55E 9" R. Pine, 95.15'  
Set nail & tag N70E Power Pole, 89.22'  
Set nail & tag N73W Power Pole, 172.10'



Signed by Eugene Farrier

Date 1-30-97

Surveyor's Michigan License No. 24594