

**SURVEY & REMONUMENTATION**

**MAR 21 1997**

**COMMISSION**

**KALKASKA COUNTY, MICHIGAN RECEIVED**

**LAND CORNER RECORDATION CERTIFICATE** 97 JAN 31 PM 2:43  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA

(County)

Located In:

Corner Code #

1996 REMONUMENTATION

1. Public Land Survey

T 26N R 6W

B-7

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Joan Hall*  
REG. OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Nov. 12, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:

B-07 cor common to Sec. 18 & 19, T26N-R6W, Oliver Township  
May 14, 1852, GLO resurvey, set post, 14" Hemlock N25E 22, 6" Sugar S50W 18.  
08-10-1880, G.A.Himpert, Co. Surveyor, used corner, no accessories.  
06-02-1902, W.S.Merrill, Co. Surveyor, used corner, no accessories.  
08-29-1904, W.S.Merrill, Co. Surveyor, fd iron stake, no accessories.  
05-17-1978, J.L.Wilcox, fd 1/2" rerod. Liber 2 pg. 299 in Survey.  
06-08-1988, E.D.Farrier, Survey #8388, fd rerod, w/ accessories.  
06-10-1988, LCRC Liber 2 pg. 388.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-07 cor common to Sec. 18 & 19, T26N-R6W, Oliver Township  
Found 1/2"x24" re-rod w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in center line of Spencer Rd. on fence line to North & South. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**

Chairman Eugene Farrier

Date 1-21-97

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-07 cor common to Sec. 18 & 19, T26N-R6W, Oliver Township  
Found 1/2"x24" re-rod w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in center line of Spencer Rd. on fence line to North & South.  
Set nail & tag N08E 10" R.Pine, 42.58'  
Set nail & tag N52E 12" R.Pine, 37.98'  
Set nail & tag S35E 4" Hemlock, 35.74'  
Set nail & tag S11W 4" R.Pine, 49.26'



Signed by Eugene Farrier

Date 1-30-97

Surveyor's Michigan License No. 24594