

SURVEY & REMONUMENTATION

MAR 21 1997

KALKASKA COUNTY, MICHIGAN
RECEIVED

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PM 2:43

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1996 REMONUMENTATION	T <u>26N</u> R <u>6W</u>	<u>C-2</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	●	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Nov. 13, 1996,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

1. Description of original monument and accessories and/or subsequent restoration:
- C-02 cor common to Sec. 5 & 6, T26N-R6W, Oliver Township
 - May 15, 1852, GLO resurvey, Set post. 30"Hemlock N65W 53, 30"Hemlock S75E 15.
 - 11-09-1972, C.L.Roser, set 1"x18" Pipe over fd Well point, no accessories.
 - 11-09-1972, LCRC Liber 1 pg.180.
 - 03-24-1973, N.F.Parker, fd 1" pipe. Liber 1 pg. 275 of Survey.
 - 06-22-1981, E.D.Farrier, Survey #5181, used corner, no accessories.
 - 08-03-1987, E.D.Farrier, Survey #12687, Liber 3 pg. 156 of Survey.
 - 08-22-1988, E.D.Farrier, Survey #12488, used corner, no accessories.
 - 09-03-1993, R.E.Pope, Survey #931038, fd 1" pipe, Liber 4 pg. 199 of Survey.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- C-02 cor common to Sec. 5 & 6, T26N-R6W, Oliver Township
Found 1"x 18" Iron Pipe and 1 1/2" Well Point. Pulled & Set 5/8" x 18"
re-rod w/ Brass cap, 1' East of centerline of North Sharon Road & on
treeline to East. No G.L.O. witnesses found. The Kalkaska Co. peer group
approved & accepted the above monument as a careful and faithful
reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *Eugene Farrier*
Date 11-21-97

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-02 cor common to Sec. 5 & 6, T26N-R6W, Oliver Township
Found 1"x 18" Iron Pipe and 1 1/2" Well Point. Pulled & Set 5/8" x 18"
re-rod w/ Brass cap, 1' East of centerline of North Sharon Road & on
treeline to East.
Set nail & tag N79E 6" R.Pine, 39.55'
Set nail & tag S35E 12" Maple, 50.08'
Set nail & tag S43W 10" R.Pine, 74.70'
Set nail & tag S74W 11" R.Pine, 56.23'



Signed by *Eugene Farrier* Date 1-30-97
Surveyor's Michigan License No. 24594