

**SURVEY & REMONUMENTATION**

MAR 21 1997

KALKASKA COUNTY, MICHIGAN RECEIVED

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PM 2:43

or corners in

KALKASKA  
(County)

Located In:

Corner Code #/

1996 REMONUMENTATION  
Public Land Survey

T 26N R 6W

C-6

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Jean Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18	●	17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER, in a field survey on Nov. 14, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

C-06 cor common to Sec. 17 & 18, T26N-R6W, Oliver Township  
1852, GLO resurvey, Set post. 26"Hemlock N85E 17, 24"Hemlock S75W 34.  
06-20-1881, E.Mosher, Co. Surveyor, used corner, no accessories.  
06-03-1884, E.Mosher, Co. Surveyor, used corner, no accessories.  
09-29-1904, W.S.Merrill, Co. Surveyor, used corner, no accessories.  
July 1979, LCRC Liber 2 pg. 185.  
08-14-1979, J.L.Fletcher, fd Pk nail. Liber 2 pg. 377 of Survey.  
05-14-1987, Farrier Surveying, Survey #6587, fd Pk nail, no accessories.  
05-15-1987, E.D.Farrier, Survey #6587, fd Pk nail replace 1/2" iron, w/ accessories.  
06-03-1988, Farrier Surveying, Survey #8388, fd iron & cap #24594, no accessories.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-06 cor common to Sec. 17 & 18, T26N-R6W, Oliver Township  
Found 1/2" x 18" re-rod w/ cap #24594 w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in centerline of North Sharon Road & online w/ fence to east. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-06 cor common to Sec. 17 & 18, T26N-R6W, Oliver Township  
Found 1/2" x 18" re-rod w/ cap #24594 w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in centerline of North Sharon Road & online w/ fence to east.  
Set nail & tag S51E 12" R.Pine, 119.40' (old witness)  
Set nail & tag S68E 10" R.Pine, 111.00'  
Set nail & tag N85W Power Pole, 46.60'  
Set nail & tag N65W 4" R.Pine, 61.15'

Ratified by Peer Group

P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 1-21-97



Signed by Eugene Farrier

Date 1-30-97

Surveyor's Michigan License No. 24594