

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

KALKASKA COUNTY, MICHIGAN RECEIVED

97 JAN 31 PM 2:43

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Joan Hall
REG. OF DEEDS

or corners in

KALKASKA
(County)

Located In:

Corner Code #/

1996 REMONUMENTATION
Public Land Survey

T 26N R 6W

C-7

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

Property Controlling
in Section

S _____ T _____ R _____

Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____

Private Claims _____

EUGENE FARRIER

Nov. 21, 1996

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

C-07 cor common to Sec. 17, 18, 19 & 20, T26N-R6W, Oliver Township
May 17, 1852, GLO resurvey, used corner. 8"Maple S22W 15. 8"Hemlock N40E 13.

08-12-1879, E.Mosher, Co. Surveyor, used corner, no accessories.

08-10-1880, G.A.Himpert, used corner, no accessories.

06-03-1884, E.Mosher, Co. Surveyor, used corner, no accessories.

07-19-1901, W.S.Merrill, Co. Surveyor, used corner, no accessories.

06-02-1902, W.S.Merrill, Co. Surveyor, used corner, no accessories.

08-29-1904, W.S.Merrill, Co. Surveyor, fd iron stake, no accessories.

09-18-1975, LCRC Liber 1 pg. 364-A.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-07 cor common to Sec. 17, 18, 19 & 20, T26N-R6W, Oliver Township
Found 5/8"x18" rebar. Pulled & Set 5/8"x18" re-rod w/ Brass cap in Mon Box 1' West of center line North Sharon Rd & in centerline Spencer Rd. No G.L.O. witnesses found. The Kalkaska Co. peer group approved and accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 1-21-97

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-07 cor common to Sec. 17, 18, 19 & 20, T26N-R6W, Oliver Township
Found 5/8"x18" rebar. Pulled & Set 5/8"x18" re-rod w/ Brass cap in Mon Box 1' West of center line North Sharon Rd & in center line Spencer Rd.

Set nail & tag N43W Power Pole, 51.95'

Set nail & tag N45E Cut off Power Pole, 41.00'

Set nail & tag S70E 13" Cedar, 124.10'

Set nail & tag S54W Support Pole, 54.62'



igned by *Eugene Farrier*

Date 1-30-97

urveyor's Michigan License No. 24594