

SURVEY & REMONUMENTATION

KALKASKA COUNTY, MICHIGAN
RECEIVED

MAR 21 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 31 PM 2:43

COMMISSION

For corners in

KALKASKA

(County)

Located In:

Corner Code ##

Jean Hall
REG. OF DEEDS

1996 REMONUMENTATION

1. Public Land Survey

T 26N R 6W

D-3

2. Property Controlling in Section

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____

2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3			●										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER

Nov. 21

19 96

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- D-03 cor common to Sec. 5 & 8, T26N-R6W, Oliver Township 1852, GLO resurvey, Set Post. 14" Sugar S45W 8, 16" Yellow Birch N60E 50. 09-29-1903, W.S. Merrill, iron stake, no accessories. 05-15-1972, LCRC Liber 1 pg.16. 05-18-1972, J.L. Wilcox, fd 1 1/4" pipe. Liber 1 pgs. 2,3,4,5&6 of Survey. 10-06-1976, J.L. Fletcher, fd 8" Boat spike. Liber 1 pg. 934 of Survey. 06-15-1988, B.M. Jones, fd Boat spike. Liber 3 pg. 228 of Survey. 06-15-1988, LCRC Liber 2 pg. 343.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-03 cor common to Sec. 5 & 8, T26N-R6W, Oliver Township Found Boat Spike & 1 1/4" x 18" Iron pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in centerline of Kniss Road. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 1-21-97

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-03 cor common to Sec. 5 & 8, T26N-R6W, Oliver Township Found Boat Spike & 1 1/4" x 18" Iron pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in centerline of Kniss Road. Set nail & tag S08W 14" Maple, 35.03' Set nail & tag S57W 30" Tw. Maple, 52.88' Set nail & tag N04W 24" Maple, 51.86' Set nail & tag N26W 12" Maple, 56.23'



Signed by *Eugene Farrier*

Date

1-30-97

Surveyor's Michigan License No. _____

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983