

**SURVEY & REMONUMENTATION**

MAR 21 1997

COMMISSION

KALKASKA COUNTY, MICHIGAN RECEIVED

LAND CORNER RECORDATION CERTIFICATE 97 JAN 31 PM 2:44  
Filing Requirement of Act 74, Mich. P.A. 1970

*Joan Hall*  
REG. OF DEEDS

For corners in

KALKASKA (County)	Located In:	Corner Code #
1996 REMONUMENTATION	T 26N R 6W	D-7
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Oct. 1, 1996  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- D-07 cor common to Sec. 17 & 20, T26N-R6W, Oliver Township May 17, 1852; GLO resurvey, Set Post. 14" Elm N57E 23, 13" Sugar S24.5W 8.
- 08-12-1879, E. Mosher, Co. Surveyor, used corner, no accessories.
- 07-19-1901, W.S. Merrill, Co. Surveyor, used corner, no accessories.
- 09-21-1972, LCRC Liber 1 pg 89.
- 04-01-1975, N.F. Parker, fd well point. Liber 1 pg. 651 of Survey.
- 04-01-1975, LCRC Liber 1 pg. 350.
- 09-18-1975, LCRC Liber 1 pg. 364-A.
- 11-06-1975, H.L. Fluharty, fd 1" pipe, Liber 1 pg. 766 of Survey.
- 05-14-1987, Farrier Surveying, Survey #6587, fd 1 1/4" well point, Also recorded in Liber 3, Pg. 127 of Survey.
- 06-07-1991, E.D. Farrier, Survey #7691, fd well point, w/ accessories.

Ratified by Peer Group  
 P.A. 345 - 1990 Kalkaska County  
 Chairman *[Signature]*  
 Date 1-21-97

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-07 cor common to Sec. 17 & 20, T26N-R6W, Oliver Township  
 Found 1 1/4" well point w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 1' South of centerline of Mecum Road & 18' East of centerline of Sohlaf Road (Private), Also 1' East of fence Occ. to 1' North & 1' West of centerline of Overhead Power to North. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-07 cor common to Sec. 17 & 20, T26N-R6W, Oliver Township  
 Found 1 1/4" well point w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 1' South of centerline of Mecum Road & 18' East of centerline of Sohlaf Road (Private), Also 1' East of fence Occ. to 1' North & 1' West of centerline of Overhead Power to North.  
 Set nail & tag N05W Power Pole, 33.09'.  
 Set nail & tag N42E 10" R. Pine, 69.05'.  
 Set nail & tag S67E 28" Maple, 85.35'.  
 Set nail & tag South service Pole, 32.36'.



Signed by *Eugene Farrier* Date \_\_\_\_\_  
 Surveyor's Michigan License No. 24594

1-30-97