

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

KALKASKA COUNTY, MICHIGAN RECEIVED

AND CORNER RECORDATION CERTIFICATE 97 JAN 31 PM 2:44
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA (County)	Located In:	Corner Code -#
1996 REMONUMENTATION		
1. Public Land Survey	T 26N R 6W	E-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ H _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jason Hall
 REG. OF DEEDS

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Nov. 21, 1996, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- E-01 cor common to Sec. 4 & 5, T26N-R6W, Oliver Township & Sec. 32 & 33, T27N-R6W, Excelsior Township
- 1852, GLO resurvey, Set Post. 10"B. Ash N29W 15, 10"B. Ash N12E 16.
- 09-19-1887, E.Mosher, Co. Surveyor, used corner, no accessories.
- 1888, E.Mosher, Co. Surveyor, used corner, no accessories.
- 09-02-1903, W.S.Merrill, Co. Surveyor, used corner, no accessories.
- 11-09-1904, W.S.Merrill, Co. Surveyor, used corner, no accessories.
- 09-02-1959, K.J.Ostling, 27lks. North of squareppst, set from 2 possible witnesses.
- 07-13-1974, LCRC Liber 1 pg. 327.
- 11-09-1978, LCRC Liber 2 pg. 136.
- 04-25-1979, J.L.Fletcher, fd. 1" iron pipe. Liber 2 pg.345 of Survey.
- 04-25-1979, LCRC Liber 2 pg. 177.
- 10-19-1982, DNR, fd 3/4" pipe, no accessories.
- 06-12-1986, N.B.DeYoung, fd 1" iron pipe, w/ accessories.
- 12-21-1987, J.L.Schwandt, fd 3/4" iron rod. Liber 3 pg 191 of Survey.
- 05-22-1990, Farrier Surveying, Survey #6490, fd 5/8" iron pipe thin wall, no accessories.
- 06-08-1990, E.D.Farrier, Survey #6490, fd 3/4" pipe, w/ accessories.

Validated by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman *Eugene Farrier*
 Date 1-21-97

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-01 cor common to Sec. 4 & 5, T26N-R6W, Oliver Township & Sec. 32 & 33, T27N-R6W, Excelsior Township
 Found 3/4" x 18" Iron Pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box 1.5' East of centerline of Sigma Road. No GLO witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-01 cor common to Sec. 4 & 5, T26N-R6W, Oliver Township & Sec. 32 & 33, T27N-R6W, Excelsior Township
- Found 3/4" x 18" Iron Pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box 1.5' East of centerline of Sigma Road.
- Set nail & tag West 4"x4" Cedar Post, 33.52'
- Set nail & tag N65E 4" Beech, 30.30'
- Set nail & tag S54E Power Pole, 57.37'
- Set nail & tag S36W 6" Beech, 45.42'

Signed by *Eugene Farrier*
 Surveyor's Michigan License No. 24594

Date 1-30-97



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISION JAN., 1983