

SURVEY & REMONUMENTATION

MAR 21 1997

KALKASKA COUNTY, MICHIGAN
RECEIVED

COMMISSIONER LAND CORNER RECORDATION CERTIFICATE 97 JAN 31 PM 2:44
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

| | | |
|--|--------------------------|---------------|
| <u>KALKASKA</u> (County) | Located In: | Corner Code # |
| 1996 REMONUMENTATION Public Land Survey | T <u>26N</u> R <u>6W</u> | <u>E-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| Property Controlling in Section | S _____ T _____ R _____ | _____ |
| Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

Jean Hall
REG. DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | | 5 | ● | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | | 17 | | 18 | | 19 | | 20 | | 21 | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

EUGENE FARRIER, in a field survey on Nov. 21, 19 96

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

E-02 cor common to Sec. 4 & 5, T26N-R6W, Oliver Township
1852, GLO resurvey, Set Post. 14" Tamarack S45E 41, 12" Tamarack N35W 16.
11-09-1978, LCRC Liber 2 pg. 136.
12-21-1987, J.L.Schwandt, fd 1/2" iron rod. Liber 3 pg.191 of Survey.
10-28-1988, G.F.DeLaMater, used corner, Liber 3 pg 272 of Survey.
10-31-1988, LCRC Liber 2 pg. 371.
08-13-1990, E.D.Farrier, Survey #9290, fd 1/2" re-rod w/ accessories.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-02 cor common to Sec. 4 & 5, T26N-R6W, Oliver Township
Found 1/2" re-rod 7' West of c\l Sigma Rd w/accessories. Pulled & set 5/8" x 18" re-rod w/brass cap in Mon. Box. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *Eugene Farrier*
Date 1-21-97

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-02 cor common to Sec. 4 & 5, T26N-R6W, Oliver Township
Found 1/2" re-rod 7' West of c\l Sigma Rd w/accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon. Box.
Fd nail N35E, 6" Balsam, 53.30'
Fd nail S85E, 1/2" rerod, 33.00'
Fd nail S55E, 6" Cedar, 39.32'
Fd nail S60W, 9" Cedar, 72.98'



igned by *Eugene Farrier*
urveyor's Michigan License No. 24594

Date 1-30-97