

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

KALKASKA COUNTY, MICHIGAN RECEIVED

LAND CORNER RECORDATION CERTIFICATE 97 JAN 31 PM 2:44
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1996 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>6W</u>	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Joan Hall
REG. DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Nov. 11, 19 96,
 to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:
 E-04 cor common to Sec. 8 & 9, T26N-R6W, Oliver Township
 1852, GLO resurvey, Set Post, 12"Beech N19W 36, 10"Beech S44E 22.
 09-29-1903, W.S.Merrill, Co. Surveyor, fd stake set iron, no accessories
 05-15-1972, LCRC Liber 1 pg. 15.
 05-18-1972, J.L.Wilcox, fd 1/2" rod. Liber 1 pgs. 2-6 of Surveys.
 09-21-1972, LCRC Liber 1 pg. 89.
 05-03-1976, J.L.Fletcher, used corner. Liber 1 pg. 872 of Survey.
 06-06-1988, E.D.Farrier, Survey #8188, used corner, no accessories.
 05-11-1992, E.D.Farrier, Survey #8092, fd 1/2" iron, Liber 4 pg. 69 of Surveys.
 05-28-1992, E.D.Farrier, Survey #8188A, fd iron cap#14102, w/ accessories. Date?, LCRC License #24594.
2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 E-04 cor common to Sec. 8 & 9, T26N-R6W, Oliver Township
 Found 1/2" re-rod & cap #14102 & 2" x 14" iron pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 1' West of c/l of Sigma Rd. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful perpetuation of the position of the original corner.
3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-04 cor common to Sec. 8 & 9, T26N-R6W, Oliver Township
 Found 1/2" re-rod & cap #14102 & 2" x 14" iron pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 1' West of c/l of Sigma Rd.
 Set nail & tag N65W 12" Red Pine, 41.18'
 Set nail & tag N39W 10" White Pine, 56.23'
 Set nail & tag N44E 10" Maple, 54.10'
 Set nail & tag S60E 10" Red Pine, 66.40'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-21-97



Signed by Eugene Farrier Date 1-30-97
 Surveyor's Michigan License No. 24594