

SURVEY & REMONUMENTATION

MAR 21 1997

KALKASKA COUNTY, MICHIGAN RECEIVED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PM 2:44

For corners in **COMMISSION**

<u>KALKASKA</u> (County)	Located In:	Corner Code -#
1996 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>6W</u>	G-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Joan Hall
REG. DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on Nov. 11, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	18	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G-01 cor common to Sec. 3 & 4, T26N-R6W, Oliver Township & Sec. 33 & 34, T27N-R6W, Excelsior Township
 1852, GLO resurvey, Set Post. 15"Hemlock N65E 19, 10"Hemlock N48W 5, 12"Hemlock S46E 27, 18"Hemlock S41W 30.
 1888, E.Mosher, Co. Surveyor, used corner, no accessories.
 09-02-1903, W.S.Merrill, Co. Surveyor, used corner, no accessories.
 08-13-1957, DNR, set 1" pipe w/ 4" brass cap, w/ accessories.
 08-02-1990, LCRC Liber 2 pg. 423.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-01 cor common to Sec. 3 & 4, T26N-R6W, Oliver Township & Sec. 33 & 34, T27N-R6W, Excelsior Township
 Found DNR Mon w/ 4" x 4" cedar DNR Post, left in place. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman *Eugene Farrier*
 Date 1-27-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-01 cor common to Sec. 3 & 4, T26N-R6W, Oliver Township & Sec. 33 & 34, T27N-R6W, Excelsior Township
 Found DNR Mon w/ 4" x 4" cedar DNR Post, left in place.
 Found nail N11W 12" Cedar, 18.77'
 Found nail N66E 10" Cherry, 11.28'
 Found nail S26E 12" Cedar, 34.84'
 Found nail S53W 12" Balsam Fir, 18.17'



Signed by *Eugene Farrier* Date 1-30-97
 Surveyor's Michigan License No. 24594