

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 22 and 27

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER


8" Maple	-	S65E	-	91 1/2 links
6" Cherry	-	S31W	-	110 1/2 links
Center of Trail	-	South	-	20 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial resurvey of this township. Set corner by proportionate measurement- midpoint, on line- between section corners. Hemlock government BTs gone, and no definite original evidence.

Corner was placed and witnessed September 22, 1959.

SURVEYORS SEAL



SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 9/25/59