

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 21-22-27-28

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER


8" Cedar	-	N28W	-	75 links
14" Cedar	-	S80W	-	47 links
14" Cedar	-	S80E	-	2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while completing a partial resurvey of this township. Set corner at government record from NW government BT, a 14" Cedar which was down but has half of upper face intact with plain marks. This position falls 2 links west of another large Cedar which was blazed on 4 sides about 60 years ago. Could not find post since it falls in fairly dry soil in roots of large Cedar. A very good specimen of original survey evidence.

Corner was placed and witnessed September 22, 1959.

SURVEYORS SEAL



SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 9/25/59