## MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

## LAND CORNER RECORD

T 26 NR 6 W

					<u>K</u>	alkaska_		COUNTY
DESCRIPTION	OF	CORNER	1/4 c	onner	common	to Secti	ons 27	3 and 24
DESCRIPTION	OF	CORNER	MONUM	ENT	<u>l"</u> pipe	e with 4"	bras	s cap
WITNESSES	ТО	CORNER _	<b></b>	· ·				
			36" W.	Pine	stump -	s48W	<b>.</b>	72 links
			6" Ma	ple	·	\$26E	<b>**</b>	48½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a resurvey of this township. Set corner by proportionate measurement between section corners. Corner falls about 2 links north of E-W fence and 32 links east of corner fence post. Could find no evidence to support the fence corner, which is about right for latitude but about 32 links out of line between section corners. Fences in this area do not lend themselves to any definate pattern of survey and must be given minimum consideration in corner restoration.

Corner was set and witnessed 10-19-59.

SURVEYOR'S SEAL

SIGNED LAND SURVEYOR

DATE 70/57/23