

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 12 and 13

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" Basswood - N54E - 4 1/2 links

7" Basswood - South - 4 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a resurvey of this township. Could not positively identify any government evidence. A possible location based on faint remains of a possible government Hemlock would be about 4 links north and 3 links east of our location. However, did not consider this sufficient evidence to restore the corner.

Corner was set and witnessed 10-20-59.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling  
REGISTERED LAND SURVEYOR

DATE 10/21/59