

Looney

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13-14-23-24
DESCRIPTION OF CORNER MONUMENT 1"x24" pipe, below road surface
WITNESSES TO CORNER

8" Maple - N38W - 72½ links
5" Maple - S23W - 62½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while completing a partial resurvey of this township. Set corner by double proportionate measurement between section corners 1 mile north, south, east, west. Could find no previous corner in road. Corner falls approximately 2' south of center of E-W county road and about 8' east of fence line north.

Corner was set and witnessed October 19, 1959.

SURVEYORS SEAL

SIGNED *Francis J. Oetting*
REGISTERED LAND SURVEYOR

DATE 10/21/59