MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

LAND CORNER RECORD

T 26 NR 6 W

| | | | Kalkasl | Ka | COU | NTY |
|----------------------|--------------|--------|----------|-------------|-----------|------------|
| DESCRIPTION OF CORNE | R 1/4 corner | _commo | n to Sec | tions_ | 3_and_4 | - . |
| DESCRIPTION OF CORNE | R MONUMENT_ | T" bib | e_with 4 | <u>bras</u> | s_cap | - |
| WITNESSES TO CORNER | | | | | | - |
| | 8" Cedar | | 882W | | 42½ links | - - |
| | 8" ASH | | S13E | | 20 Links | . <u>-</u> |
| | | | | | | |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while completing a partial resurvey of this township. Found a very old squared stake at corner, scribed 1/4 S. A down and rotted Cedar for SE government BT, which might have evidence of upper face, and Ash sprouts at site of NW government BT. This stake appeared old enough to assume that evidence of the government survey existed at the time the corner was established. Checks for distance and line south to other corners, but leaves the N 1/2 mile quite shorth.

Corner was placed and witnessed September 21, 1959.

SURVEYORS - SEAL

SIGNED CHUNTEL SURVEYOR

DATE 9/25/59_