

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.26 NR. 6 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 3 and 10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER


7" Cedar	-	S81E	-	17 links
7" W. Pine	-	N63W	-	15 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial resurvey of this township. Restored corner from probable NW government BT, a large Tamarack stump which might have evidence of BM. Hole for SE Cedar. This point checks good for line and measurement between section corners, and was considered the best available evidence of the proper position for this corner. Falls about 35 links south of apparent center of E-W road.

Corner was placed and witnessed September 21, 1959.

SURVEYORS SEAL



SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 9/25/59