

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28 and 29

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" Aspen	-	S50E	-	23 1/2 links
48" W. Pine stump	-	West	-	17 links
5" Aspen	-	N5E	-	3 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial retracement of this township. Set corner from 48" W. Pine Stump which appears to have evidence of BM, and is considered very probably the government BT. Could find no evidence of post since corner falls in roots of another pine stump. Checks stream north, and checks for line and distance to good corners north.

Corner was placed and witnessed September 2, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 9/4/59