

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 10 and 15

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" Maple - N56E - 65 links

5" Maple - S29W - 25 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial retracement of this township. Set corner from large Maple stump which is only one near and is concluded to be the SE government BT. This point checks midpoint measurement good between Section corners and is only 10 links out of line. Considered very probably the government corner and the best available evidence of the proper position for the corner.

Corner placed and witnessed September 3, 1959.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE 9/4/59