

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 9-19-15-16

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

5" Cedar	-	N16E	-	10 links
10" Cedar	-	S22E	-	27½ links
8" Cedar	-	S40W	-	39½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial retracement of this township. Found a well preserved stake point under surface of swamp at record bearing and distance from remains of NE Tamarack, both of which we conclude to be government evidence. This point checks measurement north to possible 1/4 corner and south to identified 1/4 corner Sections 15 and 16. Checks acceptably for line and distance over 1/4 and section corner east, although this mile is 50 links longer than record. Falls in old E-W winter road and nearly on old LES random. SE gov't BT falls in road.

This corner was placed and witnessed September 3, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 9/4/59