

KALKASKA ✓

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>26</u> N. S. R. <u>6</u> E. W.	A-1 B-1
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	, T. <u>26</u> N. S. R. <u>6</u> E. W.	Code <u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11-10 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-1 Reestablished corner at double distance and extension of line through SW corner & W $\frac{1}{2}$ corner of Section 6. Fits Merrill survey dated 1904 and old occupation (SW cor. of cleared field). Straight line extension of Sec. line from N. would be 18'± W. Cor. by double proportion would be 13'± E.
- B-1 Reestablished corner per standard B.L.M. instructions.
- Code 1 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1	B-1	Code 1
Set DNR Mon. & Cedar Guard Post.	Set DNR Mon & Cedar Guard Post	Set 1"x5' Pipe & Ced. Guard Post w/loc tag
12" Maple N20E 9.1	8" Tamarack S62W 52.4'	8" Tamarack S 6E 5.0'
10" Maple N88E 11.3	8" W. Pine N36W 19.2'	10" W. Pine N17E 3.8'
8" Maple S21E 23.0	7" W. Pine N88E 79.5'	10" W. Pine N66E 31.3'
N-S Woods trail	5" W. Pine S41E 53.9'	E-W Rand Due N 1.8'
Due W 15'	E-W Rand. Due N 1.0'	
Rand. South Due W 130.8'		


SIGNED BY Carl F. Roser DATE 1-11-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____